

Rec'd
2-12-15

Bid #1 Festival Lawn Concrete



Extra Work Proposal PCO 18 Date of Work _____
 Project: Festival Lawn Date of proposal 2/12/2015
 Description: Festival Sidewalk/Ramps

Labor

Name:	Description	Hours	Rate	Total
				0
				0
				0
	Superintendant	0	63.49	0
	Foreman	24	63.49	1523.76
	Labor	48	51.98	2495.04
	Operator	32	66.73	2135.36
	Mason	220	61.15	13453
Subtotal Labor				19607.16

19607.16

Equipment

Type	Description	Hours	Rate	Total
	Concrete 2 ton	16	50	800
	Skiploader	16	75	1200
	Backhoe	4	125	500
	Dump Truck	8	50	400
	Compactor	8	50	400
	Water	16	50	800
Subtotal Equipment				4100

4100

Materials

Description	Qty	Unit	Total
Sawcutting	0	1	1,000
Concrete/misc		1	15,000.00
Layout/Survey		1	1000
Misc patchback		1	2500
			0
			0
Subtotal Materials			19500

19500

	Rate	Amount	Total
Markup Sub.	0.05	0	\$ -
Markup Equipment/Materials	0.15	23600	\$ 3,540.00
Markup Labor	0.11	19607.16	\$ 2,156.79
Bond	0.01	\$ 48,903.95	\$ 489.04
Subtotal Total Cost		\$ 49,392.99	
Total Cost			\$ 49,392.99

Agency Representative _____ Date _____ Contractor's Representative *[Signature]* Date _____

Rec'd
2-12-15

Bid # 2 Festival Lawn Concrete



February 12, 2015

City of Cathedral City
68700 Avenida Lalo Guerrero
Cathedral City, CA 92234

Attn: Shawn Maddox

Re: Festival Park

Subj: Sidewalk Pricing

Dear Mr. Maddox:

Per your request, itemized below is our pricing for the installation of storm drain and drainage structures.

Item	Description	Qty	Unit	Unit Cost	Total
1	Mobilization	1	LS	\$3,000.00	\$3,000.00
2	Traffic Control	1	LS	\$4,000.00	\$4,000.00
3	Dust Control	1	LS	\$1,000.00	\$1,000.00
4	Sawcut AC Pavement	160	LF	\$2.00	\$320.00
* 5	Remove & Replace Curb and Gutter	80	LF	\$50.00	\$4,000.00 *
6	Construct 4" Thick PCC Sidewalk	6,480	SF	\$6.50	\$42,120.00
7	Construct Driveway Approach	1	EA	\$1,500.00	\$1,500.00
8	Construct Case A Ramps	3	EA	\$1,200.00	\$3,600.00
				TOTAL	\$59,540.00


1. No import or export of material is figured. Dirt will be spread/borrowed from adjacent parcel.
2. The area in front of the work will be closed during construction.
3. See attached takeoff for summary of quantities.

Sincerely,

GRANITE CONSTRUCTION COMPANY

Joe Richardson
Senior Estimator

Bid # 3



41905 Boardwalk Suite K
Palm Desert
CA, 92211
Ph. (760) 343-2861
Fax. (760) 343-3892
Lic. 800402

DATE: 2/17/2015
PROPOSAL #: 65-R
SUBMITTED TO: Cathedral City

PROJECT NAME: Sidewalk Improvements - Festival Lawn

LOCATION: Festival Lawn
Cathedral City, CA

SCOPE OF WORK:

Amount

- 1) Construct approximately 4,469 sq. ft. of 4" thick natural gray concrete city sidewalk and walkway with a regular broom finish over native soil. (Curb and gutter to be protected in place.) **\$26,814.00**
- 2) Construct approximately 2,469 sq. ft. of 6" thick natural gray concrete city pavement with a regular broom finish over native soil. (Curb and gutter to be protected in place.) **\$17,283.00**
- 3) Construct approximately 135 sq. ft. of new residential driveway approaches, (1) ea. **\$1,620.00**
- 4) Construct approximately (3) ea. Curb ramps. **\$1,800.00**
- 5) Provide and install approximately 90 sq. ft. of truncated (Armor Tile) domes. **\$4,050.00**
- 6) Remove and replace approximately 85 ln. ft. of natural gray concrete curb and gutter at new curb ramps and at new driveway approach.(Curb and gutter at sidewalk not included) **\$5,100.00**

Note: Final field measure will be done upon completion before billing.
Traffic control provided by others.
All grading and compaction to be completed by others.
Price does not include hauling away of spoils and debris.
U.B.C. is not liable for any existing curb and gutter damages.
Concrete sidewalk shall follow existing curb and gutter level.
Saw cut at asphalt not included unless noted otherwise.
Prevailing wages are included .

We Propose hereby to furnish material and labor complete in accordance with above specifications, for the sum of:

\$56,667.00

fifty six thousand six hundred and sixty seven dollars

Payment for completed work will be decided between contractor and sub-contractor

Bid #4

AIKEN CONSTRUCTION

38-251 Chuperosa lane Cathedral City California 92234
PH. 760-880-5100 AIKENCONSTRUCTIONCALIF@GMAIL.COM

ST. LIC. 834232

Interiors, Framing, Electrical, Plumbing, Concrete, Hotel, Residential, Commercial, Street work, and Structural Design

Principle: William J. Aiken, G.C.

Associate: Melissa J. Aiken, Planning and field management

PROPOSAL TO BID;

Sidewalk Improvement on the Festival Lawn


2 march 2015

Bid as per plan;

1. Cut and remove asphalts east edge.
2. Grade to 4" below finish grade and remove all dirt from site.
3. Construct 4" thick P.P.C. concrete walkway (about 86 yds)
4. Concrete to be 3,250 psi or better.
5. Construct curb ramp (3 each)
6. Construct modified concrete drive approach (1 each)
7. ALL WORK TO BE PREVAILING WAGE PAYROLL.
8. Duration of work 8 days.
9. All work will be preform by an (A) General Engineering (B) General Building and (C8) Concrete licensed contractor.
10. If accepted contract to follow.
11. Plot plan date 10 February 2015

12. BID AT \$ **42,300.00**

Respectfully submitted,



William Aiken,

Approval
